

Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
45	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes)	No	1.00	119240.00	Rupees One Lakh(s) Nineteen Thousand Two Hundred Forty Only
46	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	103420.00	Rupees One Lakh(s) Three Thousand Four Hundred Twenty Only
47	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixeign of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	1.00	106540.00	Rupees One Lakh(s) Six Thousand Five Hundred Forty Only
48	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	106500.00	Rupees One Lakh(s) Six Thousand Five Hundred Only
49	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixeign of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	107680.00	Rupees One Lakh(s) Seven Thousand Six Hundred Eighty Only
50	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeign of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	73640.00	Rupees Seventy Three Thousand Six Hundred Forty Only
51	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeign of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	81900.00	Rupees Eighty One Thousand Nine Hundred Only

Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
52	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeing of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	83490.00	Rupees Eighty Three Thousand Four Hundred Ninety Only
53	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeing of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	85650.00	Rupees Eighty Five Thousand Six Hundred Fifty Only
54	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeing of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	95780.00	Rupees Ninety Five Thousand Seven Hundred Eighty Only
55	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeing of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes)	No	1.00	85560.00	Rupees Eighty Five Thousand Five Hundred Sixty Only
56	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeing of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge.	No	1.00	84760.00	Rupees Eighty Four Thousand Seven Hundred Sixty Only
57	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixeing of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge.	No	1.00	84280.00	Rupees Eighty Four Thousand Two Hundred Eighty Only
58	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes) (inclusive of all taxes) As per approved quotation	No	1.00	84150.00	Rupees Eighty Four Thousand One Hundred Fifty Only

Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
59	Providing, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	1.00	75640.00	Rupees Seventy Five Thousand Six Hundred Forty Only
60	Providing and fixing of ornamental grill for, inside frame designs made out of 10 mm thick Hexagonal Hollow Section height 1.20m, appearance and dimension of hand railing is indicated in drawings including cost of labour etc, complete as per direction of Engineer in charge (inclusive of all taxes). including outdoor duco painting (inclusive of all taxes) As per approved quotation	No	8000.00	30.00	Rupees Thirty Only
61	Providing and Fixing the I Section ISMB 200 mm X 100 mm X 5.7 mm to support (inclusive of all taxes) (inclusive of all taxes) As per approved quotation	Rmtr	120.00	2500.00	Rupees Two Thousand Five Hundred Only
62	Providing, Fabricating and Fixing of Bull made out of welded iron link chain materials as per drawings for appearance and dimensions is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, complete as per direction of Engineer in Charge. Dimensions : (106 inch X 32 inches X 60 inches weight: 1 ton (inclusive of all taxes) As per approved quotation	No	1.00	1200000.00	Rupees Twelve Lakh(s) Only
63	Providing, Fabricating and Fixing of CAR made out of Welded Iron Automobile Parts, materials as per drawings for appearance and dimensions is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, complete as per direction of Engineer in Charge. (inclusive of all taxes) Dimensions : 108 x 120 x 33 inches Base size required : (12 x 5 feet) weight: 1.5 Ton approximately (inclusive of all taxes) As per approved quotation	No	1.00	1400000.00	Rupees Fourteen Lakh(s) Only
64	Providing, Fabricating and Fixing of DEER made out of Welded Iron Automobile Parts, materials as per drawings for appearance and dimensions is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, complete as per direction of Engineer in Charge. (inclusive of all taxes) Dimensions : 64 x 102 x 44 inches Base size required: (10.5 x 6 feet) weight: 1.5 Ton approximately (inclusive of all taxes) As per approved quotation	No	1.00	1200000.00	Rupees Twelve Lakh(s) Only
65	Providing, Fabricating and Fixing of ASHOKA PILLAR made out of Welded Iron Automobile Parts, materials as per drawings for appearance and dimensions is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, complete as per direction of Engineer in Charge. (inclusive of all taxes) Dimensions : 64 x 102 x 44 inches Base size required: (10.5 x 6 feet) weight: 1.5 Ton approximately (inclusive of all taxes) As per approved quotation	No	1.00	1850000.00	Rupees Eighteen Lakh(s) Fifty Thousand Only
66	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1(a) / 2.3.1 Note : Adopt item 2.24 for excavation in all types of soils for lowering & levelling the ground for building works by mechanical means KBS Pg No 6, Item No 2.1	Cum	340.72	263.94	Rupees Two Hundred Sixty Three And Paise Ninety Four Only
67	KSRB 2-11 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by Ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications..(P-7 Sl.no -2.11) PWD SR 2018-19	Cum	63.17	128.30	Rupees One Hundred Twenty Eight And Paise Thirty Only

Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
68	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100 mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. Specification No. KBS Pg No 7, Item No 2.15	Cum	53.35	2574.74	Rupees Two Thousand Five Hundred Seventy Four And Paise Seventy Four Only
69	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 (M7.5) with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Pg No.13 Item No 4.3	Cum	127.41	5408.12	Rupees Five Thousand Four Hundred Eight And Paise Twelve Only
70	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.460 cum, with super plasticisers @ 3 liters conforming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, column pillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6, Pg No. 14 Item No. 4.11	Cum	256.88	5998.54	Rupees Five Thousand Nine Hundred Ninety Eight And Paise Fifty Four Only
71	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - Pg No. 18 TMT bars Fe 500	Cum	15.86	75224.00	Rupees Seventy Five Thousand Two Hundred Twenty Four Only
72	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Pg No. 16 Item No. 4.46.2	Cum	449.86	483.36	Rupees Four Hundred Eighty Three And Paise Thirty Six Only
73	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification. No. KBS 2.9, Pg No.7, Item No.2.10	Cum	12.60	213.10	Rupees Two Hundred Thirteen And Paise Ten Only
74	Supplying and fixing of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975, 4 core 16 sqmm Item rate Item rate (PWD electrical S.R material list page: XVIII SL/NO 522)	Rmtr	300.00	150.00	Rupees One Hundred Fifty Only
75	Supplying heavy gauge PVC conduit pipe 20/25/32 mm dia 2mm thick conforming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary.	Rmtr	300.00	83.00	Rupees Eighty Three Only


Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
76	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50 mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency >130lm/w, nominal CRI >75. Luminaire manufacturer should have inhouse facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part.	Rmtr	20.00	8800.00	Rupees Eight Thousand Eight Hundred Only
77	Supplying and fixing of Group A, regular MCB distribution boards on wall/woodboard/flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB'S single phase/ 3 phase / single door with powder coated painting made out of SWG MS enclosure	Rmtr	10.00	1210.00	Rupees One Thousand Two Hundred Ten Only
78	Supply and fixing miniature circuit breakers on the existing MCB distribution boards using necessary fixing materials and "C" type curve, Indicator ON/OFF energy cross -3 with as required confirming to IEC 60898 Item rate As per approved Data rate	Rmtr	20.00	909.00	Rupees Nine Hundred Nine Only
79	Providing Antique decorative cast iron Electrical Pole Fabricating, supplying and erection of 7 Mtrs long hot dip IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/sec for Mtrs pole in single section and single joint welded as per IS 9595/IS 10178 AWS having dimensions bottom 350 mm, top 250 mm with 3mm thick, suitable base plate and 4 Nos of long J bolts along with template and the pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc., (excluding foundation) as per drawing appended. as per the architectural Drawing and specification as per the directions of Engineer in Charge..... Item rate As per approved Data rate	Rmtr	7.00	156000.00	Rupees One Lakh(s) Fifty Six Thousand Only
80	Providing and fixing of LED 30W lighting is indicated in drawings including cost of labour etc, complete as per direction of Engineer in charge (inclusive of all taxes). Ornamental grill for Hand Railing : PWD electrical S.R item no-12.8.2 page no-67	Rmtr	100.00	3360.00	Rupees Three Thousand Three Hundred Sixty Only
81	Conveying the excavated earth, debris etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge. Pg No 136, Item No 17.4	Cum	54.60	65.85	Rupees Sixty Five And Paise Eighty Five Only
82	14.58. Providing and fixing granite flooring in combination of 19 mm thick (Avg) gang saw water cut LAKARED granite with 86% and with 14% of 19mm thick (avg) Black granite in CM 1:4 proportion with a coat of rough plastering using CM 1:4, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification KBS 14.58, Pg No 111, Item No 14.58	Cum	520.16	3682.44	Rupees Three Thousand Six Hundred Eighty Two And Paise Forty Four Only
83	14.55, Providing full nosing for 20 mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification KBS No.14.55, Pg No.111	Cum	522.85	286.20	Rupees Two Hundred Eighty Six And Paise Twenty Only
84	KSRB 14.4 : Providing and laying flooring and steps fine dressed granite stone slabs 40 mm thick on cement mortar bed 1:6, and pointed with cement mortar 1:3 over existing cement concrete bed, including cost of materials, labour, curing complete as per specifications. Specification No. KBS 14.26 Pg No.103	Cum	12.42	3435.36	Rupees Three Thousand Four Hundred Thirty Five And Paise Thirty Six Only

Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
85	Providing and fixing Stainless steel staircase railing as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50 mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20 m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications.. Pg No. 45 Item No. 7.38	Cum	431.88	6382.26	Rupees Six Thousand Three Hundred Eighty Two And Paise Twenty Six Only
86	Providing Granite holes of 50 mm dia for fine dressed granite stone slabs 40 mm thick (As per Approved data Rate)	Cum	108.00	120.00	Rupees One Hundred Twenty Only
87	Providing and laying fine dressed granite stone pillar of 300 mm dia nd 2.5 M height including cost of materials, labour, curing complete as per specifications. (As per approved Data rate)	Cum	6.00	11000.00	Rupees Eleven Thousand Only
88	Providing and laying fine dressed granite stone pillar of 300 mm dia nd including cost of materials, labour, curing complete as per specifications. (As per approved Data rate)	Cum	6.00	5500.00	Rupees Five Thousand Five Hundred Only
89	KSRRB M300-2.2. Grassing with Doobs grass KSRRB M300- 2.1. Grassing with Doobs grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for moving including supplying good earth if needed complete as per specifications. MORTH Specification No. 307 ii) In rows 7.5 cm apart in either direction ,item No 19.79, Page:148 PWD SR 2018-19	Cum	29.54	90.10	Rupees Ninety And Paise Ten Only
90	KSRB 5.4.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6 stone Masonary in superstructure with cement mortar , edge of stones chistle dressed in courses not less than 15 cms high, bond stones at two 2M. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.4.3, Pg No 25, Item No 5.12	Cum	39.65	5683.70	Rupees Five Thousand Six Hundred Eighty Three And Paise Seventy Only
91	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400 X 200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications. KBS No.5.14, Pg No. 27 Item No. 5.26.1	Sqm	222.42	966.70	Rupees Nine Hundred Sixty Six And Paise Seventy Only
92	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 1200mm Specification No. KBS 14.47.1 Pg No.109	Sqm	943.22	2903.34	Rupees Two Thousand Nine Hundred Three And Paise Thirty Four Only
93	KSRB 6-2.3 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0Newton per sqmm (table moulded) with cement mortar 1:6 for basement and superstructu/re including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2, page no.29,item no 6.2 PWD Sr 2018-19	Cum	6.79	7112.00	Rupees Seven Thousand One Hundred Twelve Only
94	KSRB15-1.6 : Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4, to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. KBS No.15.1.6, Pg No. 115 Item No. 15.6	Sqm	208.98	216.24	Rupees Two Hundred Sixteen And Paise Twenty Four Only
95	KSRB 15-16.1 Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer item No.15.53.2 Page No. SR 2018-19	Sqm	210.06	108.12	Rupees One Hundred Eight And Paise Twelve Only

Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
96	Supplying heavy gauge PVC conduit pipe 40mm dia 2.5mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. item no-3.4,Item 3.4.1,Item 3.4.2 page no-2, PWD SR 2019-20 (40mm,dia,2.5mm thick)	Rmtr	160.00	105.00	Rupees One Hundred Five Only
97	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation.Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50 mm.Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have inhouse facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years	Each	44.00	6800.00	Rupees Six Thousand Eight Hundred Only
98	Supplying and flush modular powder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firm flush mounted after due groove cutting in brick /stone/C.C wall ... item no-1.2,Item 1.2.2,Item 1.2.3 page no-2, PWD SR 2018-19.	Each	32.00	105.00	Rupees One Hundred Five Only
99	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/niches as per IS 1293 and IS 3854.,Item 3.6.11 page no-10, PWD SR 2018-19	Each	8.00	162.00	Rupees One Hundred Sixty Two Only
100	Supplying and fixing of Group A, regular MCB distribution boards on wall/woodboard/flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB'S single phase/ 3 phase / single door with powder coated painting made out of SWG MS enclosure. item no-5.18,Item5.18.4 page no-27,28 PWD SR 2018-19.	Each	8.00	1210.00	Rupees One Thousand Two Hundred Ten Only
101	Supply and fixing miniature circuit breakers on the existing MCB distribution boards using necessary fixing materials and "C" type curve, Indicator ON/OFF energy cross -3 with as required confirming to IEC 60898 item no-5.17,Item 5.17.4. page no-27, PWD SR 2018-19.	Each	8.00	909.00	Rupees Nine Hundred Nine Only
102	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendments. item no-2.3,Item2.3.4 page no-5,6 PWD SR 2018-19.	Each	200.00	45.00	Rupees Forty Five Only
103	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.item no-5.18,page no-27, PWD SR 2019-20.	Each	8.00	1800.00	Rupees One Thousand Eight Hundred Only
104	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975, item no-6.4.2, page no-40, PWD SR 2019-20.	Rmtr	405.50	130.00	Rupees One Hundred Thirty Only
105	Providing and filling sand in excavated trench to cover already laid UG cable to a depth of 150 mm all-round the cable item 6.7,page no- 41 SR 2018-19.	mtr	360.00	100.00	Rupees One Hundred Only
-106	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1KV class UG cable filled with necessary bitumen/ insulating compound complete with terminals,lamps, bolts, nuts and washers etc. item 6.10.5,page no- 42SR 2018-19.	Each	8.00	618.00	Rupees Six Hundred Eighteen Only

Sl No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
107	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer	Sqm	1.80	92.20	Rupees Ninety Two And Paise Twenty Only
108	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60 mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS	Sqm	146.00	1116.20	Rupees One Thousand One Hundred Sixteen And Paise Twenty Only
109	KSRB M1200-48.2. Construction of cement concrete kerb with top and bottom width 115 and 165 mm respectively, 250 mm high in M-20 grade PCC on M-10 grade foundation 150 mm thick, foundation having 50 mm projection beyond kerb stone, kerb stone laid with kerb lying machine, foundation concrete laid manually, all complete as per Clause 400.8 complete as per specifications. B. Using Concrete Batching and Mixing Plant MORTH Specification No.408item No 26.127, Page no.217 PWD SR 2018-19	mtr	80.00	293.00	Rupees Two Hundred Ninety Three Only
110	Providing and laying For elevation using white sadarhalli stone with stone chiesing and fine dressed granite stone slabs 100 mm thick with cement mortar 1:3 including cost of materials, labour, curing complete as per specifications. (AS per Approved Data rate including GST)Elevation Stone for aesthithic purpose @ TOP OF WALL (1X0.3X0.1) granite size	Sqm	60.00	4850.00	Rupees Four Thousand Eight Hundred Fifty Only


Executive Engineer
 Project Division
 Yelahanka Zone
 BBMP, Bangalore-92


ಮುಖ್ಯ ಅಭಿಯಂತರರು
 ಯಲಹಂಕ ವಲಯ
 ಬಿ.ಬಿ.ಎಂ. ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ